

- GROUND WATER TABLE FOR STRUCTURAL CALCULATIONS IS BASED UPON GROUND WATER TABLE AT 5-0" ENGINEER/AUTHORITY SHALL NOTIFY OLDCASTLE PRECAST, INC. UPON REVIEW OF THIS SUBMITTAL BELOW GRADE. IF DESIGN(OR ACTUAL) WATER TABLE IS LESS THAN ASSUMED, REVIEWING

- THESE CALCULATIONS DO NOT INCLUDE ANY LATERAL OR SURCHARGE LOADS PRODUCED BY OTHER FOOTINGS OR FOUNDATIONS ADJACENT TO THIS STRUCTURE. THIS STRUCTURE SHALL BE KEPT A MINIMUM OF 1:1 RATIO AWAY FROM OTHER FOOTINGS OR FOUNDATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER COORDINATION TO ENSURE THAT AN ADEQUATE BEARING SURFACE IS PROVIDED (I.E. LEVEL AND COMPACTED) PER PROJECT SPECIFICATIONS AND DRAWINGS.
- AFTER PIPES ARE INSTALLED IN BLOCKOUTS, ALL ANNULAR SPACES SHALL BE FILLED WITH A MIN. OF 3,000 psi CONCRETE, TIGHT TO THE UNDERSIDE OF UPPER SECTION FOR FULL THICKNESS OF VAULT WALL.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO SUPPLY AND INSTALL ALL PIPING AND SAMPLING TEES.
- STRUCTURE IS NOT DESIGNED FOR INTERNAL WATER PRESSURE PRIOR TO BACKFILLING. THE CONTRACTOR SHALL BACKFILL STRUCTURE PRIOR TO TESTING OR PLACING IN SERVICE

DESIGN, AS SHOWN HEREIN, IS APPLICABLE ONLY TO STRUCTURAL PERFORMANCE OF PRECAST. CAPACITY (GALLONS) SHALL BE DETERMINED BY OTHERS BASED ON SPECIFIC PROJECT REQUIREMENTS.



PPS

EMT

SALES ORDER

REVISION ---REV DATE CHECKED

유