


GENERAL DESIGN NOTES:

- STRENGTH DESIGN METHOD IN ACCORDANCE WITH (I.A.W.) ACI 318.
- APPLICABLE DESIGN DOCUMENTS (CURRENT EDITIONS):
 - ACI 318 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE (MAIN DESIGN SPECIFICATION).
 - ASTM C890 STANDARD PRACTICE FOR MINIMUM STRUCTURAL LOADING FOR MONOLITHIC OR SECTIONAL PRECAST CONCRETE WATER AND WASTEWATER STRUCTURES (LOADING SPECIFICATION).
 - ASTM C478 STANDARD SPECIFICATION FOR PRECAST MANHOLES (PRODUCT SPECIFICATION).
- PRECAST RATED FOR HS20-44 TRUCK LIVE LOAD W/ IMPACT I.A.W. ASTM C890.
- MAX DEPTH TO INVERT OF MANHOLE (I.E. FLOOR) = 30".
- LATERAL DESIGN PRESSURES (AS APPLICABLE TO DESIGN):
 - EQUIV DRY SOIL FLUID PRESSURE = 47 PCF.
 - EQUIV SATURATED SOIL FLUID PRESSURE = 85 PCF.
 - HYDROSTATIC WATER PRESSURE = 62.4 PCF.
 - LIVE LOAD SURCHARGE = 80 PSF
- DESIGN CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS = 4,000 PSI (MIN).
- REINFORCEMENT:
 - CARBON-STEEL DEFORMED BARS: ASTM A615, $f_y = 60$ KSI (MIN).
 - WELDED WIRE REINFORCEMENT (PLAIN): ASTM A1064 $f_y = 65$ KSI (MIN).
 - WELDED WIRE REINFORCEMENT (DEFORMED): ASTM A1064 $f_y = 70$ KSI (MIN).
- JOINT SEALANT (PER CONTRACT SPECIFICATIONS):
 - CS-102 CONSEAL BUTYL RUBBER SEALANT (OR EQUIV.) I.A.W. ASTM C990 FED. SPEC. SS-S-210.
 - CS-212 CONSEAL EXTERIOR JOINT WRAP (OR EQUIV.) I.A.W. ASTM C877 AND ASTM C990.
 - CS-50 CONSEAL LIQUID BUTYL PRIMER (OR EQUIV.) AS NEEDED.
- COPOLYMER POLY PROPYLENE STEEL REINFORCED STEPS I.A.W. ASTM C478 SPACED 16" O.C.
- OPENINGS CAST OR CORED IN MANHOLE TO DEFLECTIONS AND ELEVATIONS SPECIFIED ON CONTRACT DRAWINGS MAX HOLE SIZE IS 78" (60" RCP).
- PRECAST INVERT PROVIDED UPON REQUEST: MIN $\frac{1}{2}$ " PER FT BENCH SLOPE FROM SPRINGLINE


GRADE RING

HEIGHT	WEIGHT (lbs)
4"	200
6"	300




TRANSITION SLAB

WT = 6,300 LBS.




FLAT TOP

WT = 7,400 LBS.




RISER SECTION

HEIGHT	WEIGHT (lbs)
2.00' RISER	5,800
2.67' RISER	7,300
3.00' RISER	8,050
4.00' RISER	10,950
5.00' RISER	13,200
6.00' RISER	15,450




DOGHOUSE RISER SECTION



STANDARD BASE SECTION


HEIGHT	WEIGHT (lbs)
2.00' BASE	9,100
2.50' BASE	10,225
2.67' BASE	11,350
3.50' BASE	13,225
4.00' BASE	14,350
4.67' BASE	15,850
5.00' BASE	16,600
5.67' BASE	18,100
6.00' BASE	18,850
6.33' BASE	19,600



EXTENDED BASE SECTION

HEIGHT	WEIGHT (lbs)
2.00' BASE	11,750
2.50' BASE	12,875
2.67' BASE	13,250
3.50' BASE	15,125
4.00' BASE	16,250
4.67' BASE	17,750
5.00' BASE	18,500
5.67' BASE	20,000
6.00' BASE	20,750
6.67' BASE	22,250

SCALE (TYP): 1/4" = 1'-0"



THIS DOCUMENT IS THE PROPERTY OF OLDCASTLE PRECAST, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOUS TO THE INTERESTS OF, OR WITHOUT THE WRITTEN PERMISSION OF OLDCASTLE PRECAST, INC. COPYRIGHT © 2017 OLDCASTLE PRECAST, INC. ALL RIGHTS RESERVED

7" DIAMETER MANHOLE SUBMITTAL LAYOUT

CUSTOMER

DATE	SALES	DRAWN	ENGINEER	CHECKED	SALES ORDER
6/15/17		PPS			
DRAWING NUMBER				REVISION	SHEET
7-MH-2017					1 OF 1
				REV DATE	