







PLAN VIEW N.T.S.

SECTION B-B N.T.S.

GENERAL NOTES:

- Compacted 3/4" gravel or broken stone base required for all precast units, Minimum Depth = 8".
- 2. A 18" x 8" x 4" recess to be provided in side and end walls as shown.
- 3. After installation of conduit, all open recesses are to be completely bricked and finished.
- 4. Precast Junction Box Foundation may be installed behind the guide rail or in areas where the slope is less then 1:22.
- 5. Align conduits.
- 6. Concrete strength to be 4,000 PSI @ 28 days.