GENERAL NOTES:

THE STORM CAPTURE™ SYSTEM BY OLDCASTLE PRECAST IS PART OF THE STORMWATER MANAGEMENT SYSTEM FOR THE RESPECTIVE SITE, AS PREPARED BY THE PROJECT DESIGN ENGINEER. IT IS THE RESPONSIBILITY OF THE DESIGN ENGINEER TO DETERMINE DESIGN FLOW RATES, PRE-TREATMENT AND POST-TREATMENT REQUIREMENTS, STORAGE VOLUME, AND ENSURE THE FINAL DESIGN MEETS ALL CONVEYANCE AND STORAGE REQUIREMENTS. SYSTEM DESIGN AND TYPE, SOIL ANALYSIS, LOADING REQUIREMENTS, COVER HEIGHT AND MODULE SIZE DETERMINE THE FOUNDATION TYPE AND REQUIREMENTS AS STATED HEREIN. ANY VARIATIONS FOUND DURING CONSTRUCTION FROM THE SITE AND SYSTEM ANALYSIS MUST BE REPORTED TO THE PROJECT DESIGN ENGINEER. THE PROJECT DESIGN ENGINEER IS RESPONSIBLE FOR OBTAINING A GEOTECHNICAL ENGINEERING REPORT VERIFYING THE BEARING CAPACITY STATED IN DESIGN NOTES.

DESIGN NOTES:

- 1. DESIGN LOADINGS:
 - AASHTO HS-20-44 W/ IMPACT.
 - DEPTH OF COVER = 6" 5'-0".
 - ASSUMED WATER TABLE = BELOW BOTTOM.
 - EQUIVALENT FLUID PRESSURE = 45 PCF.
 - LATERAL LIVE LOAD SURCHARGE = 80 PSF
- NO LATERAL SURCHARGE FROM ADJACENT STRUCTURES.
- CONCRETE 28 DAY COMPRESSIVE STRENGTH SHALL BE 6,000 PSI.
- STEEL REINFORCEMENT: REBAR, ASTM A-615, GRADE 60.
- CEMENT: ASTM C-150 SPECIFICATION.
- STORM CAPTURE MODULE TYPE = DETENTION.
- REQUIRED BASE LAYER DEPTH = 2" SAND BEDDING LAYER.
- REQUIRED NATIVE ALLOWABLE SOIL BEARING PRESSURE = 3,000 PSF.
- REFERENCE STANDARDS:
- ASTM C 890
- B. ASTM C 891
- ASTM C 913
- LESS THAN 6" OR GREATER THAN 5' OF COVER REQUIRES CUSTOM STRUCTURAL DESIGN AND MAY REQUIRE THICKER SUBGRADE.

INSTALLATION NOTES:

THE STORM CAPTURE™ MODULE SYSTEM IS TO BE INSTALLED IN ACCORDANCE WITH ASTM C891, INSTALLATION OF UNDERGROUND PRECAST UTILITY STRUCTURES. PROJECT PLAN AND SPECIFICATIONS MUST BE FOLLOWED ALONG WITH ANY APPLICABLE REGULATIONS.

- PLAN LINE, GRADE AND ELEVATIONS MUST BE FOLLOWED.
- WHERE SPECIFIED, AN 8 OZ. NON-WOVEN GEOTEXTILE FABRIC MUST BE USED AS A SEPARATION LAYER AROUND THE STORM CAPTURE SYSTEM.
- PENETRATIONS IN THE GEOTEXTILE MAY ONLY BE MADE WITH SMOOTH WALL PIPES. MAKE PENETRATIONS FOR ALL OUTLETS BEFORE MAKING PENETRATIONS FOR ANY INLETS.
- ALL SUBGRADE MATERIALS IF SPECIFIED, MUST BE CLEAN, DURABLE CRUSHED AGGREGATE COMPACTED OR ROLLED TO ACHIEVE 95% STANDARD PROCTOR DENSITY. OLDCASTLE RECOMMENDS SIZE 5.56.OR 57 (PER ASTM C33).
- DESIGNATED EMBEDDED LIFTERS MUST BE USED. USE PROPER RIGGING TO ASSURE ALL LIFTERS ARE EQUALLY ENGAGED WITH A MINIMUM 60 DEGREE ANGLE ON SLINGS AS NOTED AND IN ACCORDANCE WITH OLDCASTLE LIFTING PROCEDURES.
- MODULES MUST BE PLACED AS CLOSE TOGETHER AS POSSIBLE, AND GAPS SHALL NOT BE GREATER THAN 3/4". ALL EXTERIOR SYSTEM JOINTS SHALL BE COVERED WITH A MIN. 8" JOINT WRAP ON SIDES AND TOP (CS-212 CONSEAL OR EQUIVALENT). IN A CLAMSHELL DESIGN INSTALL ONE ROW CS-102 CONSEAL (OR EQUIVALENT) BETWEEN PRECAST PIECES.
- AUTHORIZATION SHOULD BE GIVEN BY THE PROJECT ENGINEER OR DESIGNATED PERSON PRIOR TO PLACEMENT ON BACKFILL FOR THE SYSTEM. CARE SHOULD BE TAKEN DURING PLACEMENT OF BACKFILL NOT TO DISPLACE MODULES OR JOINT WRAP. BACKFILL SHALL BE COMPACTED TO 95% STANDARD PROCTOR DENSITY OR AS SPECIFIED, AND SHOULD NOT BE COMPACTED WITHIN 6" OF MODULE.
- CONSTRUCTION EQUIPMENT EXCEEDING DESIGN LOADING SHALL NOT BE ALLOWED ON STRUCTURE
- TERMADUCTS TO BE KNOCKED OUT AT SPECIFIED LOCATIONS IN FIELD BY OTHERS. SEE SITE LAYOUT FOR LOCATIONS.

INLETS AND RISERS:

ALL PIPE INLETS SHALL EXTEND INSIDE MODULE A MINIMUM OF 4". PLACE A NON-SHRINK, NON-METALIC GROUT, MIN. 3,000 PSI IN ANNULAR SPACE TO ELIMINATE ALL VOIDS.

REVISIONS								
REVISION	DATE	SHEETS	SHEETS DESCRIPTION OF REVISION					



TABLE OF CONTENTS

NOTE: THIS VIEW IS FOR ILLUSTRATION PURPOSES ONLY TO SHOW FEATURES OF

PROJECT, SEE SITE PLAN LAYOUT. ALL

PERIMETER WALLS ARE SOLID.


THE SYSTEM ACTUAL LAYOUT VARIES BY

NOTES & GENERAL ISO

TYPICAL ELEVATION

EXTERIOR DETAILS

INTERIOR DETAILS



BOTTOM MODULE WITH TOP SLAB ISO VIEW

THIS MUST BE FILLED OUT BEFORE MANUFACTURING BEGINS

APPROVED W/ NO EXCEPTIONS TAKEN:

APPROVED AS NOTED:

REVISE AND RESUBMIT:

- PRELIMINARY -NOT FOR CONSTRUCTION

SIGNATURE



7921 SOUTHPARK PLAZA, SUITE 200, LITTLETON, CO 80120 PHONE: 1-888-965-3227 FAX: 303-794-7497 THIS DOCUMENT IS THE PROPERTY OF CLIDCASTLE PRECAST, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOD TO THE INTEREST OF, OR WITHOUT THE WRITTER PREMISSION OF COL

STORMCAPTURE


NOTES & GENERAL ISO

SALES ORDER SALES | DRAWN | ENGINEER CHECKED STS STS JH

SC - 5 ft base with too slab

1 OF REV DATE





NOTE: TERMADUCT INSERTS TO BE KNOCKED OUT AT SPECIFIED LOCATIONS ONLY (BY OTHERS).

- PRELIMINARY - NOT FOR CONSTRUCTION




THIS DOCUMENT IS THE PROPERTY OF OLDCASTLE PRECAST, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOUS TO THE INTERESTS OF, OR WITHOUT THE WRITTEN PREMISSION OF LOCASTLE PRECAST, INC. COPYRIGHT 62016 OLDCASTLE PRECAST, INC. ALL RIGHTS RESERVED

STORMCAPTURE

TYPICAL ELEVATION


CUSTOMER

DATE	DATE SALES		DRAWN ENGINEER		SALES ORDER		
	STS	STS	JH				
	DRAWING N	REVISION	SHEET	_			
SC -	5 ft base v	REV DATE	2 OF 4				






KEYWAYS MUST BE FREE OF DIRT, ROCKS, AND WATER. ROCKS AND DIRT PREVENT THE VAULT SECTIONS FROM SEATING AND SEALING PROPERLY. REMOVE ALL PROTECTIVE PAPER FROM RUBBER SEALANT MATERIAL. SPLICE RUBBER SEALANT MATERIAL WITH A "SIDE BY SIDE" JOINT, AWAY FROM CORNERS. CORNER SPLICING WILL NOT SEAL PROPERLY.




CORRECT - INSTALL RUBBER SEALANT MATERIAL AT THE OUTER EDGE OF THE KEYWAY. RUBBER SEALANT SHOULD BE CONTINUOUS AROUND CORNERS.

BY PROJECT DESIGN ENGINEER




INCORRECT — DO NOT OVERLAP THE RUBBER SEALANT MATERIAL AT SPLICE.



INCORRECT - DO NOT SPLICE RUBBER SEALANT MATERIAL AT A CORNER. RUBBER SEALANT SHOULD BE CONTINUOUS AROUND CORNERS.

CONSEAL CS-102 BUTYL RUBBER SEALANT PLACEMENT DETAIL

NTS



- 8" MIN. WIDE STRIP OF SELF-ADHESIVE OVER ENTIRE JOINT. PROVIDE MIN. 1' OVERLAP WHEN CONNECTING STRIPS. JOINT WRAP SUPPLIED BY OLDCASTLE AND INSTALLED BY OTHERS. SEE INSTALLATION NOTE 6.

MODULE JOINT DETAIL SCALE: 1/2" = 1'-0"

- PRELIMINARY - NOT FOR CONSTRUCTION



THIS DOCUMENT IS THE PROPERTY OF OLDCASTLE PRECAST, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOU TO THE INTERESTS OF, OR WITHOUT THE WRITTER PREMISSION OF OLDCASTLE PRECAST, INC. COPYRIGHT 62016 OLDCASTLE PRECAST, INC ALL RIGHTS RESERVED

STORMCAPTURE EXTERIOR DETAILS

CUSTOMER

DATE	SALES	DRAWN	ENGINEER	CHECKED	SALES ORDER		
	STS	STS	JH				
	DRAWING N	REVISION		SHEET			
SC-	5 ft base v	REV DATE	3	OF	4		

MIN. 30" MANWAY ACCESS PROVIDED FOR EACH MAINTENANCE MODULE.

STORM CAPTURE MODULES BY OLDCASTLE PRECAST INC.


PIPE PENETRATION TO BE SEALED TO LINER WITH BOOT FOLLOWING LINER MANUFACTURERS RECOMMENDATIONS (INSTALLATION BY OTHERS)


PIPE ENTRANCE AS REQUIRED


MANWAY ACCESS DETAIL

SCALE: 3/8" = 1'-0"


STORMCAPTURE°








TOP SLAB LIFTING DETAIL N.T.S.





- PRELIMINARY - NOT FOR CONSTRUCTION



THIS DOCUMENT IS THE PROPERTY OF CUDCASTLE PRECAST, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOU. TO THE INTERESTS OF, OR WITHOUT THE WRITEN PREMISSION OF OLDCASTLE PRECAST, INC. COPYRIGHT 62016 OLDCASTLE PRECAST, INC. ALL RIGHTS RESERVED.

STORMCAPTURE INTERIOR DETAILS

CUSTOMER

DATE	SALES	DRAWN STS	ENGINEER JH	CHECKED	SALES ORDER
SC-	DRAWING N 5 ft base v	REVISION REV DATE	SHEET 4 OF 4		