

1"Ø Pick Holes

48" x 48" Parkway or Traffic
2 Pc. Boltdown Galv. Frame &
Cover Marked "Electric"

2 Ton Swiftlifts
2 Ea. Side Wall
4 Total

6"

Optional
12" Riser
6" Riser

1 5/8" x 1 5/8" x 36"
Unistruts
1 Ea. Wall
4 Total

4'-10" 4'-0"

4'-10" 4'-0"

3'-11"

1"Ø Ground Rod
Knockouts
1 Ea. Opp.
Corner 2 Total

2 Ton Swiftlifts
4 For Stripping
4 For Placing
8 Total

12" x 16" x 3"
Knockouts 2 At
Ea. Corner

7/8"Ø Pull Irons
1 Ea. Side Wall
4 Total

7"Ø Sump

CU 1600-14A

Overall Outside Dimensions
4'-10"W x 4'-10"L x 53"H

Overall Inside Dimensions
4'-0"W x 4'-0"L x 48"H

Minimum Excavation Is To
Be 12" Larger Than Product

On All Sides

Approximate Weights
Top - 800 Lbs
Base - 4500 Lbs
6" Riser - 600 Lbs
12" Riser - 1200 Lbs

SCALE: 3/8" = 1'-0"



Southern California
Fontana, San Diego, Santa Paula
Phone: 800-626-3860 Fax: 909-428-3737

ANAHEIM 4448HL

FILE NAME: 070UEH4448HANA.DWG

ISSUE DATE: May 2001

www.oldcastleprecast.com

4'-0" x 4'-0" x 4'-0"
Holeliner
City of Anaheim

Copyright © 2008 Oldcastle Precast, Inc.