

4' x 5' x 8" Plug
Use Felt Between Plug & Neck

2 Ton Swiftlifts
2 Ea. Side Wall
4 Total

9" x 18" Knockouts
2 Ea. Side Wall
4 Total

Identification Spot

Traffic Cover and Frame
AFCO A1106 or Equal

4' x 5' x 12" Neck Ring
Optional Risers Are Available
and Are Positioned Between
The Vault and The Neck Ring

7/8"φ Pull Irons
1 Ea. End Wall
2 Ea. Side Wall
6 Total

2 Ton Swiftlifts
4 Total

12"φ Knockouts
2 Total

Base Section
Available In
00", 6", 18", 46"

7/8"φ Pull Iron
1 Total

4 Ton Swiftlifts
4 Total

18" x 44" Deep Recess Knockout
1 Ea. End Wall
2 Total

14"φ Vent Knockouts
2 Total

Top Section

1"φ PVC. Pipe With Plastic Plug
2 Ea. Corner
8 Total

Minimum Excavation Is To Be
12" Larger Than Product On
All Sides

Overall Outside Dimensions

G1	00" Base	5'-0"W	8'-10"L	6'-9"H
G2	6" Base	5'-0"W	8'-10"L	7'-3"H
G3	18" Base	5'-0"W	8'-10"L	8'-3"H
G7	46" Base	5'-0"W	8'-10"L	10'-7"H

Overall Inside Dimensions

G1	00" Base	4'-0"W	6'-6"L	5'-6"H
G2	6" Base	4'-0"W	6'-6"L	6'-0"H
G3	18" Base	4'-0"W	6'-6"L	7'-0"H
G7	46" Base	4'-0"W	6'-6"L	9'-4"H

Approximate Weights
Top - 11500 Lbs
Base 0" - 2600 Lbs
Base 6" - 3000Lbs
Base 18" - 4700 Lbs
Base 46" - 9200 Lbs

SCALE: 1/4" = 1'-0"



Southern California
Fontana, San Diego, Santa Paula
Phone: 800-626-3860 Fax: 909-428-3737

LADWP 46684VT

FILE NAME: 070UEE466VLT.LA.DWG

ISSUE DATE: June 2004

www.oldcastleprecast.com

4'-0" x 6'-6" x 7'-0"
Vault G291
Los Angeles D.W.P.

Copyright © 2008 Oldcastle Precast, Inc.