

2 Ton Swiftlifts
2 Ea. Side Wall
4 Total

Identification Spot

36" x 60" Keyed
Opening For Riser

36" x 60" Torsion Hinged
Parkway Frame & Cover W/
Polymer Covers.

4 Ton Swiftlifts
4 Total

27 Hole Racking
1 Ea. End Wall
Flush Mounted
2 Total

4 Ton Swiftlifts
4 Total

4"Ø Terminators
1 Ea. End Wall
2 Total

4'-10"

4'-0"

1'-10"

27 Hole Racking
3 Ea. Side Wall
Mounted On 'S' Brackets
6 Total

8'-10"

8'-0"

2'-9"

7/8"Ø Pull Iron
2 Plcs. In Base

12"Ø Sump

4"Ø Terminators
3 Ea. End Wall
6 Total

Overall Outside Dimensions
4'-10"W x 8'-10"L x 5'-0"H
Overall Inside Dimensions
4'-0"W x 8'-0"L x 48"H
Minimum Excavation Is To Be
12" Larger Than Product On
All Sides

Approximate Weights
Top - 5000 Lbs
Base - 6600 Lbs

SCALE: 3/8" = 1'-0"



Southern California
Fontana, San Diego, Santa Paula
Phone: 800-626-3860 Fax: 909-428-3737

VERIZON 4848VT

FILE NAME: 070UTT4848VTVZ.DWG

ISSUE DATE: July 2001

www.oldcastleprecast.com

4'-0" x 8'-0" x 4'-0"
Vault
Verizon

Copyright © 2008 Oldcastle Precast, Inc.