

7/16" x 1'-10" x 5'-1" Protective Barrier Panels 3 Req'd

Steel Closure Plate  
5'-6 1/4" x 10" x 1/4"

Identification Spot

30" R.P.M Cover With A1106 Frame and Gasket  
Optional A1106 Traffic Cover Is Available

Recessed Lifting Pin

6'-3 1/2"

11'-4"

30" Clear Manhole Opening

5'-1" x 5'-1" Opening

4 Ton Swiftlifts  
2 Ea. Side Wall  
4 in Base  
8 Total

Top Section

3/16"x6"x4'-11"  
Galv. Plate  
Protective Panel  
Support 2 Req'd

4'-0"

3'-6"

1/2"φ Grounding Inserts  
3 Ea. End Wall  
6 Total

5'-0"

10'-6"

4'-0"

7/8"φ Pull Irons  
2 Ea. End Wall  
8 Total  
Top and Bottom

Base Section

3'-6"

6"

5"φ Terminators  
12 Ea. End Wall  
24 Total

12"φ Sump

Overall Outside Dimensions  
6'-3 1/2"W x 11'-4"L x 8'-0"H  
Overall Inside Dimensions  
5'-0"W x 10'-6"L x 7'-0"H  
Minimum Excavation Is To Be  
12" Larger Than Product On  
All Sides

Approximate Weights  
Top - 10200 Lbs  
Base - 12100 Lbs

SCALE: 1/4" = 1'-0"



**Oldcastle Precast**



UTILITY VAULT™ Division

Southern California  
Fontana, San Diego, Santa Paula  
Phone: 800-626-3860 Fax: 909-428-3737

**EDISON 510684PMH**

FILE NAME: 070UEE5106PMHE.DWG

REVISED: Jan. 2007

[www.oldcastleprecast.com](http://www.oldcastleprecast.com)

**5'-0" x 10'-6" x 7'-0"**  
**Pmh UGS #590.1**  
**Southern Calif Edison**

Copyright © 2008 Oldcastle Precast, Inc.