



Total Standard Necking
Parkway 30" - Traffic 24"

A1134 Traffic Cover and Frame
A1136 Parkway Cover and Frame
Are Also Available

36" To 30" Reducer Ring
Available In 9" and 6" Heights

4 Ton Swiftlifts
4 Total

OPTIONAL
3" Riser
6" Riser
12" Riser

7" x 35" x 3 1/2" Deep
Intercept Knockouts
1 Ea. End Wall
2 Total

5"Ø Knockouts
4 Ea. Side Wall
2 Ea. End Wall
12 Total

4 Ton Swiftlifts
4 For Stripping
4 For Placing
8 Total

4"Ø Terminators
9 Ea. End Wall
Top and Base
36 Total

6'-10"
6'-0"
3'-9"

24 Hole Cable Rack *
Flush Mounted

24 Hole Cable Rack *
Mounted On "S" Brackets

12" x 12" Corner Bracking
W/ 24 Hole Cable Rack
Typ In Every Corner
Top and Base

12"Ø Sump

Base Section

Overall Outside Dimensions
6'-10"W x 12'-10"L x 8'-1/2"H
Overall Inside Dimensions
6'-0"W x 12'-0"L x 7'-0"H
Minimum Excavation Is To Be
12" Larger Than Product On
All Sides

* Note: Single 47 Hole Cable Racks May
Be Supplied In Place Of (2) 24 Hole Cable Racks

7/8"Ø Pull Irons
2 Total

Approximate Weights
Top - 15300 Lbs
Base - 14200 Lbs

SCALE: 1/4" = 1'-0"

Oldcastle Precast
UV UTILITY VAULT Division
Southern California
Fontana, San Diego, Santa Paula
Phone: 800-626-3860 Fax: 909-428-3737

AT&T 61284MH
FILE NAME: 070UTT612MHATT.DWG
ISSUE DATE: Feb. 2008
www.oldcastleprecast.com

AT&T 6'-0" x 12'-0" x 7'-0"
Manhole
Copyright © 2008 **Oldcastle Precast, Inc.**