



4 Ton Swiftlifts
4 For Stripping
4 For Placing
8 Total

Overall Outside Dimensions
7'-10"W x 14'-10"L x 9'-7 3/4"H
Overall Inside Dimensions
7'-0"W x 14'-0"L x 8'-0"H
Minimum Excavation Is To Be
12" Larger Than Product On
All Sides

Approximate Weights
Top - 20600 Lbs
Base - 19800 Lbs

SCALE: 3/16" = 1'-0"



Southern California
Fontana, San Diego, Santa Paula
Phone: 800-626-3860 Fax: 909-428-3737

EDISON 71496VLT

FILE NAME: 070UEE714VLTED.DWG

ISSUE DATE: June 2004

www.oldcastleprecast.com

7'-0" x 14'-0" x 8'-0"
Vault UGS #410.3
Southern Calif Edison

Copyright © 2008 Oldcastle Precast, Inc.