



Approximate Weights
Top - 20600 Lbs
Base - 19800 Lbs

4 Ton Swiftlifts
4 For Stripping
4 For Placing
8 Total

Overall Outside Dimensions
7'-10"W x 14'-10"L x 9'-7 3/4"H
Overall Inside Dimensions
7'-0"W x 14'-0"L x 8'-0"H
Minimum Excavation Is To Be
12" Larger Than Product On
All Sides

SCALE: 3/16" = 1'-0"