



GROUP	LENGTH
1A	14'-0"
2	17'-0"
3A	19'-0"
4	22'-0"
5A	24'-0"
7	27'-0"
8A	29'-0"
9A	32'-0"

Approximate Weights
 End Walls - 17500 Lbs
 Access - 28800 Lbs
 Intermediate - 11400 Lbs
 3'-0" - 11400 Lbs
 5'-0" - 18900 Lbs

SCALE: 3/16" = 1'-0"

Overall Outside Dimensions
 7'-0"W x 10'-1"L x Length Varies
 Overall Inside Dimensions
 6'-0"W x 9'-0"L x Length Varies
 Minimum Excavation Is To Be
 12" Larger Than Product On
 All Sides



Southern California
 Fontana, San Diego, Santa Paula
 Phone: 800-626-3860 Fax: 909-428-3737

LADWP 894IntTunnel

FILE NAME: 070UEE894TVILA.DWG

ISSUE DATE: June 2004

www.oldcastleprecast.com

8'-0" x 9'-4" x Length Varies H172 Intercept Tunnel Vault Los Angeles D.W.P

Copyright © 2008 Oldcastle Precast, Inc.